

**NOTICE INVITATING TENDER****OFFICE OF THE DIGP, GC, CRPF, NAGPUR (MAHARASHTRA)-440 019**Email: - [diggcngr@crpf.gov.in](mailto:diggcngr@crpf.gov.in)

Ph. No. 07104 – 297 724 (Control Room)

Tender Notice No. B-II-28/2020-21-GCN-Bldg (SAP)

Dated the July , 2020

**E-TENDER NOTICE**

DIGP GC, CRPF NAGPUR for and on behalf of the President of India invites online tenders under two bid system (**Technical and Financial bid**) from Govt. (Centre/State) registered firms/contractors for **Repairing/Renovation of 54 Nos. Toilet with Front passage area for T-I (Spl) Qtr. 9 Block (193 to 198, 229 to 234, 235 to 240, 205 to 210, 199 to 204, 241 to 246, 247 to 252, 211 to 216, 217 to 228)** at GC, CRPF, Nagpur District - Nagpur (Maharashtra) – 440 019.

1. Bids will be accepted online at e-Procurement website <http://eprocure.gov.in/eprocure/app> (CPPP) and CRPF website <http://crpf.nic.in/tender-notice.htm>.
2. All relevant details, including specification, terms & conditions etc are available on at e- Procurement website <http://eprocure.gov.in/eprocure/app> (CPPP) and **CRPF website <http://crpf.nic.in/tender-notice.htm>** and same may be downloaded by the bidders.
3. For any changes/amendment in Tender Enquiry/Specifications etc, Tenderers are requested to visit the CRPF /CPPP web sites regularly.
4. The EMD is : Rs. 55,000/-
5. Date of availability of tender on CRPF website : 1100 hrs on 10/08/2020.
6. In case of any problem please contact on telephone number 07104-297724(Control Room).
7. Copy of license issued by Central or State Govt./Union territory/CPWD registration details of appropriate class.
8. Copy of Labour license issued by the State/Central Govt.

**Sd/- 18/07/2020****(Sanjay Kumar)****DIGP, GC CRPF,NAGPUR****For and on behalf of the  
President of India**

**OFFICE OF THE DEPUTY INSPECTOR GENERAL OF POLICE , GC, CRPF, NAGPUR**  
**(MAHARASHTRA) - 440 019**

Tender Notice No. B-II-28/2020-2021-(SAP)

Dated of the 18/07/ 2020

//TENDER //

Online bid/e-tenders are invited from Govt (Central/State) registered firms/contractors for **Repairing/Renovation of 54 Nos. Toilet with Front passage area for T-I (Spl) Qtr. 9 Block (193 to 198, 229 to 234, 235 to 240, 205 to 210, 199 to 204, 241 to 246, 247 to 252, 211 to 216, 217 to 228)** at GC, CRPF, Nagpur District - Nagpur (Maharashtra) – 440 019 as per details given below.

**A) SCHEDULE TO TENDER**

Schedule to Tender No.		:	B-II-28/2020-2021-(SAP) dated 18/07/2020				
Last date and time of receipt of on-line & Manual documents of tender		:	08/08/2020 at 1100 hrs				
Time and date of on-line opening e-tender		:	10/08/2020 at 1100 hrs				
Validity of offer		:	The tender shall remain open for acceptance till 180 days from the date of opening of Tender.				
Sl. No.	Ref. No.	Name of work & Location	Earnest Money	Estimated cost	Period of Completion	Last date & time of Submission of tender	Time & date of opening of tender
01	B-II-28/2020-2021-(SAP)	Repairing/Renovation of 54 Nos. Toilet with Front passage area for T-I (Spl) Qtr. 9 Block (193 to 198, 229 to 234, 235 to 240, 205 to 210, 199 to 204, 241 to 246, 247 to 252, 211 to 216, 217 to 228) at GC, CRPF, Nagpur (Maharashtra) –19	Rs. 55,000/-	Rs. – 26,90,839/-	Within 45 days from the date of award of contract	08/08/2020 at 1100 hrs	10/08/2020 at 1100 hrs

Tender will be accepted upto: -

08/08/2020/2020 at 1100 hrs

Tender will be Opened:-

10/08/2020 at 1100 hrs

Details of Work is placed at

: Appendix-A

**APPENDIX-‘A’****(A) Repairing/Renovation of 54 Nos. Toilet with Front passage area for T-I (Spl) Qtr. 9 Block (193 to 198, 229 to 234, 235 to 240, 205 to 210, 199 to 204, 241 to 246, 247 to 252, 211 to 216, 217 to 228) at GC, CRPF, Nagpur (Maharashtra) –19.**

SL No.	DSR, 18	Description of Items	Unit	Qty			
1	2	Earth Work					
2	2.1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge:					
3	2.1.1	All kinds of soil	sqm	500			
4	2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.					
5	2.8.1	All kinds of soil.	cum	60			
6	2.10	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m :					
7	2.10.1	All kinds of soil					
8	2.10.1.2	Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia	metre	150			
9	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	cum	50			
10	4	Concrete Work					

11	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :					
12	4.1.10	1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size)	cum	25			
13	5	Reinforcement Cement Concrete					
14	5.1	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :					
15	5.1.2	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size)	cum	5			
16	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level					
17	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	500			
18	6	Brick Work					
19	6.2	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in:					
20	6.2.2	Cement Mortar 1:6 (1 cement : 6 coarse sand).	cum	15			
21	10	Steel Work					
22	10.5	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer.					
23	10.5.2	Using flats 30x6mm for diagonal braces and central cross piece	sqm	25			

24	11.36	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	sqm	0			
25	11.39	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete.	sqm	66			
26	13	Finishing					
27	13.1	12 mm cement plaster of mix :					
28	13.1.1	1:4 (1 cement: 4 fine sand)	sqm	100			
29	13.48.3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture	sqm	110			
30	13.90	Distemping with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade :					
31	13.90.1	Old work (one or more coats)	sqm	1200			
32	14	Repairing of Building					
33	14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-					

		Charge.					
34	14.1.1	With cement mortar 1:4 (1 cement : 4 fine sand)	sqm	120			
35	14.5	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty:					
36	14.5.1	Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)	sqm	50			
37	13.88	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	sqm	1200			
38	17	Sanitary Installation					
39	17.1	Providing and fixing water closet squatting pan (Indian type W.C. pan ) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:					
40	17.1.1	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	each	54			
41	17.35	Providing and fixing soil, waste and vent pipes					
42	17.35.1	100 mm dia					
43	17.35.1.1	Sand cast iron S&S pipe as per IS: 1729	metre	45			
44	18	Water Supply					
45	18.10	18.10 Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc.					
46	18.10.1	15 mm dia nominal bore	meter	15			
47	18.10.3	25 mm dia nominal bore	meter	12			
48	18.10.5	40 mm dia nominal bore	meter	5			

49	18.46	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) :					
50	18.46.1	15 mm nominal bore	each	12			
51	18.46.3	25 mm nominal bore	each	10			
52	18.46.5	40 mm nominal bore	each	15			
53	18.49	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 :					
54	18.49.1	15 mm nominal bore	each	54			
55	18.52	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931.					
56	18.52.1	15 mm nominal bore	each	54			
57	18.62	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P./ H.P.H.D. plastic ball.					
58	18.62.3	25 mm nominal bore, 152mm long, weighing not less than 440 gms each	each	9			
59	22	Water Proffing					
60	22.5	Providing and laying water proofing treatment in sunken portion of WCs, bathroom etc., by applying cement slurry mixed with water proofing cement compound consisting of applying :					
61		(a) First layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/ sqm. This layer will be allowed to air cure for 4 hours.					
62		(b) Second layer of slurry of cement @ 0.242 kg/sqm mixed with water proofing cement compound @ 0.126 kg/sqm. This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours.					
63		(The rate includes preparation of surface, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry.)	Sqm	800			
64	19	Drainage					
65	19.6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :					
66	19.6.2	150 mm dia. R.C.C. pipe	Meter	120			

67	19.6.3	250 mm dia. R.C.C. pipe	Meter	150			
68	19.7	Constructing brick masonry manhole in cement mortar 1:4 ( 1 cement : 4 coarse sand ) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone- III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design :					
69	19.7.1	Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) :					
70	19.7.1.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	each	25			
71	19.7.2	Inside size 120x90 cm and 90 cm deep including C.I. cover with frame (medium duty) 500 mm internal diameter, total weight of cover and frame to be not less than 116 kg (weight of cover 58 kg and weight of frame 58 kg) :					
72	19.7.2.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	each	5			
73	19.8	Extra for depth for manholes :					
74	19.8.1	Size 90x80 cm					
75	19.8.1.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	metre	3			
76	19.8.2	Size 120x90 cm					
77	19.8.2.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	metre	1			
78	14.73	Providing and fixing bright finished brass casement window fasteners or peg stays to windows/ ventilators with necessary welding and machine screws etc. complete.	kg	54			
79	9	Wood & PVC Door					



80	9.123	Providing and fixing factory made door frame (single rebate) made out of single piece extruded solid PVC foam profile with homogenous fine cellular structure having smooth outer integral skin having 62 mm width & 32 mm thickness, frame will be mitred & Jointed with self driven self tapping screws of size 38 mm x 4 mm & PVC solvent cement, including fixing the frame to wall with suitable dia & length anchor fastener as per manufacturer's specification and direction of Engineer-in-charge.	Meter	297.72			
81	9.124	Providing and fixing factory made 30 mm thick door shutter made of solid PVC foam profile. The styles & rails shall be of size 75 mm x 30 mm having wall thickness 5 mm. The styles, top & bottom rails shall have one side wall thickness of 15 mm integrally extruded on the hinge side of the profile for better screw holding power. The styles and rails shall be reinforced with M.S. tubes of size 33 mm x 17 mm x 1 mm, painted with primer , all four corners of reinforcement to be welded or sealed. Solid PVC extruded bidding (push fit type) will be set inside the styles and the rails with a cavity, to receive single piece extruded 5mm PVC sheet as panel. The styles and rails will be mitred cut and joint with the help of PVC solvent cement & self driven self tapping screws. Single piece extruded solid PVC lock rail of size 100 mm x 30 mm with wall thickness 5 mm & 15 mm integrally extruded in the middle of the lock rail & fixed with styles with the help of PVC solvent cement & self driven self tapping screws of size 100mm x 8 mm complete as per manufacturer's specifications and direction of Engineer-in-charge.					
82	9.124.1	Non decorative finish	Sqm	105.3			

**B. Terms and conditions are asunder:**

1. Eligibility of Contractor/ Firm	<p>1. The Tenderer should be a Govt. Approved registered Central/State contractor for the subject work. The enlistment of the contractors should be valid on the last date of submission of tenders. In case only the last date of opening of tender is extended, the enlistment of contractor should be valid on the original date of opening of tenders. A copy of Registration Certificate/License issued by State/Central Govt and its related required document for the above work is mandatory to submit with the tender documents by the tenderer (s).</p> <p>2. Non CPWD registered contractors shall have to fulfill the criteria of satisfactory execution of works as given below :-</p> <p>(i) Three similar works, each of value not less than 40% of the estimated cost put to tender, <b>or</b></p> <p>(ii) Two similar works, each of value not less than 60% of the estimated cost, <b>or</b></p> <p>(iii) One similar work of value not less than 80% of the estimated cost, all amounts rounded off to a convenient full figure, in the last 7 years ending on the last day of the month previous to the one in which the tenders are invited.</p>
2. Terms of Price	<p>(a) Rates quoted by the Contractor should be in Indian Rupees both in figures as well as in words for complete units as per specifications any and every alteration in the rates should be signed in ink otherwise the offers will not be considered.</p> <p>(b) Contractor should clearly indicate different taxes and duties, which they propose to charge as extra along with the present rates thereof. Offers with such stipulations like as applicable" will be treated as vague and are liable to be ignored.</p>
3. Payment terms	<p>(a) Works are required to be executed on <b>credit basis only</b> and payment will be made after drawl of amount from RPO, CRPF, Hyderabad.</p> <p>(b) Payment in advance or immediately cannot be made.</p> <p>(c) The Payment action will be processed on production of the following documents:</p> <p>a) Bill in Triplicate.</p> <p>b) A Copy of award of work.</p> <p>(c) TDS, Labour Cess and other taxes will be deducted from the Bill of contractor by PAO as per norms.</p>
4. Earnest Money Deposit	<p>1. All the contractors are required to deposit required <b>Earnest money Off line</b></p> <p>2. The earnest money can be deposited through any of the following alternative forms: (a) A <b>TDR/ FDR</b> drawn in favour of <b>THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)</b>. [<b>Bankers: SBI, NAGPUR, (Code No.01632)</b>].</p> <p>(b) An <b>irrevocable Bank Guarantee</b> of any nationalized, scheduled bank or reputed commercial bank in the attached format as at <b>Appendix-B</b>.</p> <p>(c) The earnest money shall remain valid and to be deposited with the purchaser for a <b>period of 180 days</b> from the date of tender opening. If the validity of the tender is extended, the validity of the Bank Guarantee/or any other alternate document submitted in lieu of earnest money will also be suitably extended by the tenderer, failing which their tender after the expiry of the aforesaid period shall not be considered by the purchaser.</p> <p>(d) <b>No interest</b> shall be payable on the earnest money deposited by the tenderer.</p> <p>(e) The earnest money deposited <b>is liable to be forfeited</b> if the tenderer withdrawn or Amends impairs or derogates from the tender in any respect within the period of validity of his tender.</p>

	<p>(f) The earnest money of the successful tenderer shall be returned after the security deposit as required in terms of the contract is furnished by the tenderer. If the successful tenderer fails to furnish the security deposit as required in the contract within the stipulated period, the earnest money shall be treated as performance security deposit for all practical purposes.</p> <p>(g) Earnest money deposits of all the unsuccessful tenderers will be returned as early as possible after the expiry of bid's validity, but not later than 30 days after placement of contract. Tenderers are advised to send a <b>pre receipt challan</b> along with their bids so that refund of earnest money can be made in time.</p> <p>(h) Any tender, where the tenderer is required to deposit earnest money in terms of Conditions mentioned in preceding paras, not accompanied with earnest money in anyone of the approved forms acceptable to the competent authority, shall be summarily rejected.</p>
<p>5. Performance Guarantee</p>	<p><b>1.</b> The successful contractor shall have to deposit a Performance guarantee <b>equivalent to 5% of the tendered value</b> of the work to be executed <b>within 07 days from the date of award of contract</b> for due performance. Failure on the part of the firm to Deposit the Performance guarantee within the stipulated time empowers the competent authority to cancel the contract.</p> <p><b>2.</b> The Performance guarantee submitted by the supplier will remain valid at least <b>for 120 days beyond the date of completion of work as well as all contractual obligations of the supplier including guarantee/ warrantee obligations.</b></p> <p><b>3.</b> The performance guarantee can be deposited in any of the following alternative forms :</p> <p>(a) A <b>FDR/ TDR</b> drawn in favour of <b>THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA). [Bankers: SBI, NAGPUR, (Code No.01632).</b></p> <p>(b) An <b>irrevocable Bank Guarantee</b> of any nationalized/Scheduled Bank or reputed commercial bank in <b>any other form prescribed.</b></p> <p><b>4.</b> If the contractor fails to start the work within the stipulated period and places and requests for extension of time, he shall submit an undertaking on Non Judicial stamp paper of Rs.10/- duly attested by the Notary public stating that the performance guarantee has already been extended for sixty days beyond the guarantee/ warrantee period.</p> <p><b>5.</b> The Performance guarantee shall be withheld or forfeited in full or part in case the work order is not executed satisfactorily within the stipulated period or requisite standard within the guarantee period is not undertaken to the best satisfaction of the user.</p>
<p>6. Security deposit</p>	<p><b>The security deposit @ 2.5% of the gross amount of the bill</b> shall be deposit through <b>FDR</b> in favour of <b>THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA). [Bankers: SBI, NAGPUR, (Code No.01632).</b> The security deposit shall be refunded to the contractor after <b>expiry of defects liability period.</b></p>
<p>7. Two Bid System</p>	<p><b>1. Technical Bid:</b> Scanned copy of Documents (technical bid) submitted Online and hard copy duly attested to be dropped manually in the <b>Office of The DIGP GC CRPF NAGPUR,</b> with in time frame <b>so as to reach on or before 08/08 /2020 at 1100 hrs .</b> Department is not responsible for any postal delay as well as technical problem at portal/site. Following documents must be attached:-</p> <p>i) The bidder/ tenderer will submit the tender documents completed and signed</p>

	<p>(all pages to be signed) with seal.</p> <p>ii) Attested photo Copies of the following documents :- PAN, GST registration, Last 3 year's tax returns, service registration and DD/ P.O. /FDR/ TDR towards EMD.</p> <p>iii) Tender acceptance letter.</p> <p>iv) Complete postal address of contractor/ firm along with copy of valid I/ Card/ Voter I/D card etc</p> <p>v) Form 68(A) (As per Appendix-H)</p> <p>vi) Last 02 Years Performance/Experience certificate of similar works.</p> <p>vii) Copy of license issued by Central or State Govt./Union territory/CPWD registration details of appropriate class.</p> <p>viii) Copy of Labour license issued by the State/Central Govt.</p> <p><b>Financial Bid</b> :Indicating item/schedule wise price quoted for the work (with rates, GST, duties, if any) must be clearly mentioned in figures as well as in words and in INR as per schedule of quantity–Attachment-(1) mentioned in the technical bid.</p> <p>3. The technical bids are to be opened at the first instance and evaluated by the competent authority. In the second stage, financial bids of only the technically acceptable offers will be opened for further evaluation and ranking before awarding the contract.</p> <p>4. Online financial bid shall be opened only of those bidders who on the basis of eligibility/ technical documents uploaded by them within the period of bid submission, qualify in accordance with the provision of eligibility.</p>
--	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

7. **WORK SPECIFICATION**

The work shall be carried out according to C.P.W.D. Specifications 2018 Vol-I & II including up to date corrections and as per additional conditions.

8. **SITE VISIT AND COLLECTING LOCAL INFORMATION**

Before tendering, the tenderer is advised to visit the site, its surroundings to assess and satisfy themselves about the local conditions such as the working and other constraints at site, approach roads to the site, availability of water & power supply, application of taxes, duties and levies as applicable, accommodations they may require etc & any other relevant information required by them to execute complete scope of work. The tenderer may obtain all necessary information as to risks, weather conditions, contingencies & other circumstances (insurgencies etc.) which may influence or affect their tender prices. Tenderer shall be deemed to have considered site conditions whether he has inspected it or not and to have satisfied himself in all respect before quoting his rates and no claim or extra charges whatsoever in this regard shall be entertained / payable by **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** at a later date.

9. **VALIDITY OF TENDER**

The tender for the works shall remain open for acceptance for a period **180** days from the date of opening of Price Bid of tenders. The earnest money will be forfeited without any prejudice to any right or remedy, in case the contractor withdraws his tender during the validity period or in case he changes his offer to his benefits which are not acceptable to **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)**. The validity period may be extended on mutual consent.

10. **REJECT/CANCEL/SCRAP**

The Competent Authority has got the right to accept or reject/cancel/scrap the tender as whole or part of it and no claims what so ever will be entertained on this account. The competent authority also reserves the right to increase/decrease/alter the scope of work/ quantity of work etc. and no claims what so ever will be entertained.

#### **11. TERMINATION OF CONTRACT ON DEATH OF CONTRACTOR**

Without prejudice to any of the right or remedies under this contract if the contractor dies, **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** shall have the option of terminating the contract without compensation to the contractor. If the contractor is an individual or proprietary concern and individual or the proprietor dies or if the contractor is a partnership concern and one of the partner dies then unless, **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** is satisfied that the legal representative of the individual for the proprietary concern or the surviving partners are capable of carrying out and completing contract, he **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** is entitled to cancel the contract for the uncompleted part without being in any way liable for any compensation payment to the estate of deceased contractor or to the surviving partners of the contractor's firm on account of the cancellation of contract. The decision of **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** in such assessment shall be final and binding on the parties. In the event of such cancellation **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** shall not hold the state of deceased contractor and/or the surviving partners of the contractor's firm liable for any damages for non-completion of contract.

#### **12. DIRECTION FOR WORKS**

All works to be executed under the contract shall be executed Under the direction and subject to approval in all respect of **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** /Work Committee / Officer commanding of Building / Engineer-in-Charge of **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** who shall be entitled to direct at what point or points and in what manner works are to be commenced and executed.

#### **13. DEFECT LIABILITY PERIOD**

- i) **12 Months** from the date of Completion as certified by **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** /Officer commanding of Building Branch / Work Committee.
- ii) The contractor shall stand guarantee for materials and workmanship. During the defect liability period, if any defect is observed due to workmanship or from any act or omission of the contractor, the contractor shall execute all such work of rectification and making good of defects, as may be required of him by competent authority at his own cost and within the time stipulated by competent authority. If the contractor shall fail to do any such work as required by the competent authority, Security/ Retention money shall be liable to be forfeited and the contractor shall make him-self liable to be blacklisted.

**14.** Before starting the work the contractor shall chalk out a program, in consultation with **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** or his authorized representative at least one week in advance. The contractor shall have to adhere to this programme failing which he shall be held responsible for any inconvenience caused to the occupants. In order to ensure that the work is carried out

according to the programme drawn, the contractor shall ensure adequate supply of the material and employ required labour strength for execution of work. The contractor shall put his authorized representatives daily at the site of work / Enquiry Office for receiving instructions from **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** and other inspecting officials from the department. His name and signature shall be attested by the contractor and kept on the record with the department.

15. Payment shall be made to contractor only after giving certificate about satisfactory completion of work. All measurement shall be recorded on standard measurement sheets which will be submitted to **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** for scrutiny and passing.
16. **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** /Works committee/Officer commanding of Building/ Engineer in-charge shall scrutinize and check the measurement records practically/on ground based on the measurement sheet provided by contractor and final measurement sheet will be prepared by Engineer-in-charge of this office.
17. Dispute in mode of measurement: In case of dispute as to the mode of measurement not covered by the contract to be adopted for any item of work, mode of measurement as per latest Indian specification shall be followed.
18. Intending tenderer is eligible to submit the bid provided he has definite proof from the appropriate authority, which shall be to the satisfaction of the competent authority, of having satisfactorily completed similar works of magnitude specified.
19. **The time allowed for carrying out the work will be within 45 days from the date of work order.**
20. The site for the work is available or the site for the work shall be made available in parts as specified above.
21. The contractor shall not be permitted to tender for works in the CRPF in which his near relative of CRPF is involved. If so, he shall also intimate the names of persons who are working with him in any capacity or are subsequently employed by him and who are near relatives to any CRPF officer/personnel.
22. **Department will not be responsible for any kind of incident involving the labour during or after the work. The contractor must insure the workers against all contingencies and be responsible for their safety.**
23. **GST No. or/ and Service Tax No. and Contractor's Registration No. must be printed on the bill which is submitted for recoupment/ payment action.**
24. The tender for the works shall remain open for acceptance for a period of **180 Days** from the date of opening of tenders. If any tenderer withdraws his tender before the said period or issue of letter of acceptance, whichever is earlier, or makes any modifications in the terms and conditions of the tender which are not acceptable to the department, then **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** shall, without prejudice to any other right or remedy, be at liberty to forfeit the earnest money as aforesaid. Further the tenderer shall not be allowed to participate in the retendering process of the work.
25. The contractor shall bear cost of **Liquidated Damage** for Delay in completion of work within the stipulated time @ of **2%** per month of contracted value not exceeding the 10% of contracted value in whole.

26. This Notice Inviting Tender shall form a part of the contract document.
27. Hard copies as submitted physically in the office of **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA-440 019)**, shall be only valid document for evaluation of technical specification. **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)**, has all rights to break contract at any time without assigning any reason.
28. The Tenderer are requested to return a copy of this Tender duly signed on each page along with other relevant documents as required with the tender for evaluation purpose. If tenderer fails to return a copy of this Tender duly signed, his offer will not be considered and it will be rejected.
29. The tenderer shall be responsible for arranging and maintaining at his-own cost all materials, tools & plants, water, electricity access, facilities for executing work and all other services required for executing the work.
30. The successful tenderer shall make his-own arrangement for storage and watch and ward of material whether the same brought by him or supplied by the department. He shall remain responsible for watch and ward of installation and other fittings till these are commissioned and handed over to the department.

Successful tenderer should be in a position to produce, after opening of the price bids, the Original Certificates in support of the self attested copies of relevant documents submitted along with tender document. Failure to produce the original certificates at this stage in support of the attested copies of firm registration / Electrical License/any other documents etc. submitted earlier would result in disqualification and forfeiture of EMD and also liable for debarring from participation in the office of **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)**. [Bankers: SBI, NAGPUR, (Code No.01632) tenders.

31. **FINAL INSPECTION:** - After completion of work as per specification the whole work will be subject to a final inspection to ensure that job has been completed as per requirement. If any defects noticed in the work are attributable to Contractor, these shall be attended by the Contractor at his own cost, as and when they are brought to his notice by **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** /Work committee/officer Commanding of Building/ Engineer in charge **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)**, and its representative shall have the right to have these defects rectified at the risk and cost of the contractor if he fails to attend to these defects immediately.
32. Work scope may be changed depending upon the priority of the work.
33. No part of the CONTRACT nor any share or interest therein shall in any manner or degree be transferred, assigned or sublet by the CONTRACTOR directly or indirectly to any person, firm or corporation whatsoever without the consent in writing of **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** All materials required to be used on works shall be got approved from **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** / Officer Commanding of Building in advance. In case of doubt on any material, **THE DIGP, GROUP CENTRE, CRPF, NAGPUR (MAHARASHTRA)** wears the right to get the material test from Govt. approved labs/ NABL
34. The quoted rate should be inclusive of all taxes, levies, works contract taxes, duties etc.

35. All items to be used in this work should be branded and ISI. In this case CPWD approved list of material for similar work may be followed.
36. In any case of dispute GCC maintenance work 2019 given at [cpwd.gov.in](http://cpwd.gov.in) will be adhered to.

**Sd/- 18/07/2020**  
**(Sanjay Kumar)**  
**DIGP GC, CRPF, NAGPUR (MAHARASHTRA)**  
For and on behalf of the president of India